

FINNSEMENTTI

A CRH COMPANY

Vakavien tapaturmien ennaltaehkäisy - Projekti- / Kunnossapitoesimerkki

Jari Porkka

11.5.2023




SISÄLTÖ

1. Lappeenrannan tehtaan klinkkerituotannon prosessi ja SRF Projektin rajaus
2. Projektin haasteet
3. Projektin turvallisuusjohtaminen
4. Projektin turvallisuusjohtaminen ja sen hyödyt lyhyesti



Lappeenrannan tehtaan klinkkerituotannon prosessi ja SRFPprojektin rajaus

2

Klinkkerin tuotanto



SRF polttoaineen syöttöprojekti



Projektin haasteet

4

Projektin haasteet

- Projektin toteutus prosessin käydessä
 - Projektin sisällä kaksi kokonaisuutta
 - Rakennus
 - Laitetoimitus/asennus
 - → miten vastuut ja vastaavan työnjohtajan rooli
 - Ulkomainen toimittaja, joka tehnyt aiemmin projekteja Finnsementille → vanhat oletukset
 - Korona, joka aiheutti toimitusten viivästyksiä
 - Miten pysytään aikataulussa
-

Projektin turvallisuusjohtaminen

3

Turvallisuussuunnittelu ja Johtaminen

SRF-Project safety rules & Risk assesment - Turvallisuusasiakirja(Finnsementti)

Best Hall Overall risk assesment

Best Hall site safety plan

- Overall rules & mgmt practises
- Introduction plan
- Site plan

Job safety reviews

- Selected construction phases

Specific instructions:

- lifting plans, support instructions

Lindner Safety Plan follow up (Suunnitelmien seuranta) →

Approach based on safety rules & risk assesment

Lindner site safety plan

- Overall rules and mgmt practises
- Introduction plan
- Site plan

Job safety reviews

- Based on Safety plan follow up


Specific instructions:

- Machine specific assembly plans

Turvallisuus osana kokonaisprojektia

- Lähtökohtana Suomen laki ja CRH Life Saving Rules
- Osallistetaan suunnittelija miettimään myös asennusta
- Riskikartoituksen mukaan määritä kokonaisuudet jotka vaativat erillisen työtapaselostus (kaikki taakan siirrot, nostot, tuennat, korkealla työskentely, tasot, aukot)
- Tee työtapaselostus hyvissä ajoin, jotta pystyt varaamaan tarvittavan henkilöstön, työkalut, materiaalit sekä nostoapuvälineet
- Valvo, että suunnitelmiä toteutetaan → aloita heti alussa tiukasti
- Säännölliset auditoinnit ja palautteet
- Riskiarvio suunnitelmasta poikkeamiseen

Turvallisuus osana kokonaisprojektia – Aluesuunnitelu



Finnsementti Calsiner REF and Ammonia truck traffic transport routes always have to be maintained available.

Transport routes are described with green and orange lines

Riskikartoituksen toimenpiteiden seuranta

FINNSEMENTTI							
Lappeenranta SRF Feeding line				Not needed(Explain basis as comment)			
Needed safety plans				Needed			
				More complex plan needed		Version	V01
				Work in Progress			
				Done			
Work number				Done more complex plan		Updated	8.6.2022
						Done by	EbenbergerE
Device Code	latest delivery date	Device Name	Pre-installation JSR	Preinstallation lifting plan	Installation JSR	Installation Lifting Plan	Responsible person
1		prework for mechanical installation					Gietler Horst
2	1.8.2022	steel plates for asphalt ground			finished		Eric Ebenberger
3	.0390 17.10.2022	steel constr. 1st part - MULTIFLEX system					Eric Ebenberger
4	.0400 15.8.2022	MultiFlex system					Eric Ebenberger
	.0421 21.8.2022	Rotary valve - MULTICELL			finished		Eric Ebenberger
5	.0391 15.8.2022	steel constr. 2nd part - MULTIFLEX system					Eric Ebenberger
6	.0380 15.8.2022	magnetic drum			finished		Eric Ebenberger
7	.0320 15.8.2022	EcoDock station 1			finished		Eric Ebenberger
8	.0340 15.8.2022	EcoDock station 2			finished		Eric Ebenberger
9	.0360 15.8.2022	drag chain conveyor - MultiFlex					Eric Ebenberger
10	.0310 1.8.2022	steel construction 1st part - WF-trucks			finished		Eric Ebenberger
11	.0311 15.8.2022	steel construction 2nd part - WF-trucks			50 %		Eric Ebenberger
12	.0280 12.9.2022	feeding drag chain conveyor 1 - WF-trucks					Eric Ebenberger
13	.0300 12.9.2022	feeding drag chain conveyor 2 - WF-trucks					Eric Ebenberger
14	.0260 12.9.2022	distribution drag chain conveyor					Eric Ebenberger
15	.0240 1.8.2022	drag chain conveyor to feeding stations			finished		Eric Ebenberger
16	0.220 1.8.2022	discharge drag chain conveyor PK2800			Finished		Eric Ebenberger
17	.0200 12.9.2022	Power Komet 2800			90 %		Kari Strandvall
18	.0203 12.9.2022	FireFly system					Eric Ebenberger
19	.0130 17.10.2022	Steel construction - BG Optibulk			50 %		Eric Ebenberger
20	.0120 12.9.2022	Double screw conv. - BG Optibulk			70 %		Eric Ebenberger
21	.0101 17.10.2022	Chain belt conveyor - BG Optibulk			70 %		Eric Ebenberger
22	.0100 17.10.2022	housing - BG Optibulk			70 %		Eric Ebenberger
23	.0180 1.8.2022	Chain belt conveyor ChainCon					Eric Ebenberger
24	.0140 1.8.2022	Storage bunker MFB 550					Eric Ebenberger
25	.0160 10.10.2022	Moveable belt conveyor FlatCon					Eric Ebenberger
26	.0150 10.10.2022	Covering - bunker MFB 550					Eric Ebenberger
27	.0151 10.10.2022	Platform - bunker MFB 550					Eric Ebenberger
28	.0180 1.8.2022	Chain belt conveyor - bunker MFB 550					Eric Ebenberger
29	.0443 10.10.2022	Filter - dedusting system					Eric Ebenberger
30	.0441 10.10.2022	Ventilator - dedusting system					Eric Ebenberger
31	.0444 10.10.2022	Sound absorber - dedusting system					Eric Ebenberger
32	.0442 10.10.2022	Rotary valve - dedusting system					Eric Ebenberger
33	.0445 10.10.2022	Piping - dedusting system					Eric Ebenberger
34	.0424 10.10.2022	piping - MultiFlex system					Eric Ebenberger
35	0.600 10.10.2022	compressed air piping					Eric Ebenberger
36		Completion work plant					Eric Ebenberger
37	.0510 12.9.2022	Container - control cabinet					Eric Ebenberger
38	.0511 12.9.2022	Container - FireFly system					Eric Ebenberger
39		Cabling plant					Eric Ebenberger
40		Electrical connection plant components					Eric Ebenberger
41		no load test					Eric Ebenberger
42		warm commissioning, load test					Eric Ebenberger
43		performance test					Eric Ebenberger
44		General plan for the site area					FINNSEMENTTI

Riskikartoituksen toimenpiteiden seuranta

FINNSEMENTTI							
Lappeenranta SRF Feeding line				Not needed(Explain basis as comment)			
Needed safety plans				Needed			
				More complex plan needed		Version	V01
				Work in Progress			
				Done			
Work number				Done more complex plan		Updated	8.6.2022
						Done by	EbenbergerE
Device Code	latest delivery date	Device Name	Pre-installation JSR	Preinstallation lifting plan	Installation JSR	Installation Lifting Plan	Responsible person
1		prework for mechanical installation					Gietler Horst
2	1.8.2022	steel plates for asphalt ground			finished		Eric Ebenberger
3	.0390 17.10.2022	steel constr. 1st part - MULTIFLEX system					Eric Ebenberger
4	.0400 15.8.2022	MultiFlex system					Eric Ebenberger
	.0421 21.8.2022	Rotary valve - MULTICELL			finished		Eric Ebenberger
5	.0391 15.8.2022	steel constr. 2nd part - MULTIFLEX system					Eric Ebenberger
6	.0380 15.8.2022	magnetic drum			finished		Eric Ebenberger
7	.0320 15.8.2022	EcoDock station 1			finished		Eric Ebenberger
8	.0340 15.8.2022	EcoDock station 2			finished		Eric Ebenberger
9	.0360 15.8.2022	drag chain conveyor - MultiFlex					Eric Ebenberger
10	.0310 1.8.2022	steel construction 1st part - WF-trucks			finished		Eric Ebenberger
11	.0311 15.8.2022	steel construction 2nd part - WF-trucks			50 %		Eric Ebenberger
12	.0280 12.9.2022	feeding drag chain conveyor 1 - WF-trucks					Eric Ebenberger
13	.0300 12.9.2022	feeding drag chain conveyor 2 - WF-trucks					Eric Ebenberger
14	.0260 12.9.2022	distribution drag chain conveyor					Eric Ebenberger
15	.0240 1.8.2022	drag chain conveyor to feeding stations			finished		Eric Ebenberger
16	0.220 1.8.2022	discharge drag chain conveyor PK2800			Finished		Eric Ebenberger
17	.0200 12.9.2022	Power Komet 2800			90 %		Kari Strandvall
18	.0203 12.9.2022	FireFly system					Eric Ebenberger
19	.0130 17.10.2022	Steel construction - BG Optibulk			50 %		Eric Ebenberger
20	.0120 12.9.2022	Double screw conv. - BG Optibulk			70 %		Eric Ebenberger
21	.0101 17.10.2022	Chain belt conveyor - BG Optibulk			70 %		Eric Ebenberger
22	.0100 17.10.2022	housing - BG Optibulk			70 %		Eric Ebenberger
23	.0180 1.8.2022	Chain belt conveyor ChainCon					Eric Ebenberger
24	.0140 1.8.2022	Storage bunker MFB 550					Eric Ebenberger
25	.0160 10.10.2022	Moveable belt conveyor FlatCon					Eric Ebenberger
26	.0150 10.10.2022	Covering - bunker MFB 550					Eric Ebenberger
27	.0151 10.10.2022	Platform - bunker MFB 550					Eric Ebenberger
28	.0180 1.8.2022	Chain belt conveyor - bunker MFB 550					Eric Ebenberger
29	.0443 10.10.2022	Filter - dedusting system					Eric Ebenberger
30	.0441 10.10.2022	Ventilator - dedusting system					Eric Ebenberger
31	.0444 10.10.2022	Sound absorber - dedusting system					Eric Ebenberger
32	.0442 10.10.2022	Rotary valve - dedusting system					Eric Ebenberger
33	.0445 10.10.2022	Piping - dedusting system					Eric Ebenberger
34	.0424 10.10.2022	piping - MultiFlex system					Eric Ebenberger
35	0.600 10.10.2022	compressed air piping					Eric Ebenberger
36		Completion work plant					Eric Ebenberger
37	.0510 12.9.2022	Container - control cabinet					Eric Ebenberger
38	.0511 12.9.2022	Container - FireFly system					Eric Ebenberger
39		Cabling plant					Eric Ebenberger
40		Electrical connection plant components					Eric Ebenberger
41		no load test					Eric Ebenberger
42		warm commissioning, load test					Eric Ebenberger
43		performance test					Eric Ebenberger
44		General plan for the site area					FINNSEMENTTI

Job Safety Review –part 1 & 2

Job Safety Review Form			
Date:	Reviewed by:	Workers Name:	
Job Description:		1. GIETLER Horst	
Mechanical installation of belt conveyor Pos.160		2. KOVACEVIC Dzenis	
		3. JURICA Flis	
		4.	
		5.	
		6.	
Permits Required:	Y\N	Inspection Required:	Y\N
LOTOTO:	N	Lifting:	Y
Hot Work:	N	Crane:	Y
Hoisting\Rigging:	Y	Mobile Equipment:	Y
Confined Space:	Y	Ladders:	Y
Digging\Excavation:	N	Scaffolding:	N
Chemical dangers:	N	Equipment:	N
		Tools:	Y
Other:	N	Other:	N
Additional Comment: other applicable requirements of Finnish working act, Finnish safety regulation, plant specific safety regulations and procedures		Check PPE required at the plant and PPE required for the specific task. Remember, if task includes hoisting\rigging\lifting, you always need to restrict the area Operators of machinery need to have the right qualifications	
Sequence of Job Tasks:	Hazards\Risks:	Harm: (Possible Harmful Consequences)	Control Measures: (including additional PPE for each task)
Connect belt conveyor and bring it at place	Falling of parts, squeezing, traffic on site	Damage to personnel, damage to material	Lift the belt conveyor (weight appr. 5.000kg) with 2x telehandlers 5t and shown equipment, attach to the provided lifting points (Pic 1). Drivers should use radios to coordinate the lifting of the conveyor ! Secure the lifting area during the lifting process !
Position belt conveyor at installation place	Falling of parts, squeezing, traffic on site	Damage to personnel, damage to material	Bring the belt conveyor with 2x telehandlers 5t to the installation place (Pic 2). Drivers should use radios to coordinate the driving to the installation place. Worker at the scissor lift must give the required instructions for the correct positioning of the conveyor (by using of radio). Secure the lifting area during the lifting process !
Chains On:		Hoses Coiled Up:	
Tools Returned:		PPE Not Left:	
Ladders Returned:		Equipment Checked:	
		Equipment Tested:	

forklift 5to





telehandler 5t




scissor lift (height 8m)



Safety equipment - STOPS FALLING !




Picture 1



appr. 5.000kg




Picture 2



INSTALLATION ACC: MANUEL "48492-50" (WESTERIA)

Job Safety Review –part 3


LIFTING PLAN - BELT CONVEYOR Pos. 160



Step 1

Connect belt conveyor to telehandlers and lift it up


The driver of the green telehandler (1) gives the necessary order / instructions to the driver of the blue telehandler (2).



Step 2

Drive with belt conveyor to installation place

Guy at the scissor lift gives the required instructions with radio to driver 1 at the green telehandler (1).
The driver of the green telehandler (1) gives the necessary order / instructions to the driver of the blue telehandler (2).



Step 3

Position the belt conveyor at the correct place

Guy at the scissor lift gives the required instructions with radio to driver 1 at the green telehandler (1).
The driver of the green telehandler (1) gives the necessary order / instructions to the driver of the blue telehandler (2).

Projektin turvallisuusjohtaminen ja sen hyödyt lyhyesti

5

Turvallisuusjohtaminen osana suunnittelua

- Lyhyempi turvallinen asennusaikataulu
- Vähemmän yllätyksiä
- Parempi kustannushallinta



Turvallisuusjohtaminen osana suunnittelua



Kiitos

Jari Porkka

Finnsementti Oy

Projektipäällikkö
